Amendments to the Claims:

Please amend claims 1-7 and 9. This listing of claims will replace all prior versions, and listings of claims in the application:

Listing of Claims:

Claim 1 (currently amended): A method of cleaning, dewatering, [and] or hydrostatic testing a pipeline between two subsea manifolds, one of said manifolds having a subsea pig launcher/receiver with a pig and the other having a subsea pig receiver comprising:

providing a subsea skid comprising one or more pumps including at least one high pressure pump dimensioned to provide a hydrostatic pipeline testing pressure;

using a submersible vehicle (SV) to deploy the subsea skid to one of the subsea manifolds;

using a submersible vehicle (SV) to operate one or more pumps, on a fill and test package to force seawater behind said pig and move said pig from the pig launcher/receiver to the pig receiver, and

using said SV to <u>supply</u> power <u>to</u> at least one of <u>said</u> <u>the</u> one or more pumps to pump more water into said pipeline to a high-pressure hydrostatic test pressure and maintaining said pressure to assure that there are no leaks in said pipeline for the cleaning, dewatering, or hydrostatic testing of the pipeline.

Claim 2 (currently amended): A method according to claim 1 wherein the test pressure is read on a gauge mounted on a panel on said pig launcher/receiver at least one high pressure pump is a low volume high pressure pump and the subsea skid further comprises at least one high volume pump.

Claim 3 (currently amended): A method according to claim [2] 1 wherein said fill and test package is carried by said SV the subsea skid is held by the SV during the cleaning, dewatering, or hydrostatic testing of the pipeline.

Claim 4 (currently amended): A method for cleaning and hydrostatic testing a subsea pipeline between two manifolds, one of said manifolds having a subsea pig launcher/receiver with a pig and the other having a pig receiver comprising:

providing a fill and test package comprising one or more pumps including at least one high pressure pump dimensioned to provide a high-pressure hydrostatic test pressure;

using a submersible vehicle (SV) to deploy the fill and test package to one of the manifolds;

using [[a]] the SV operating to operate at least one pump on [[a]] the fill and test package to force seawater behind said the pig and move the pig from the pig launcher/receiver to the pig receiver; and

operating at least one of said one or more pumps high pressure pump to pump more seawater into said pipeline to a high-pressure hydrostatic test pressure and maintaining said pressure to assure that there are no leaks in [said] the pipeline.

Claim 5 (currently amended): A method according to claim 4 wherein said SV has a robotic arm for connecting and disconnecting said the pump to said the pipeline.

Claim 6 (currently amended): A method for hydrostatic testing of a pipeline before its ends are connected wherein both ends are on the seafloor comprising:

high pressure pump dimensioned to provide a high-pressure hydrostatic test pressure; using a submersible vehicle (SV) to deploy the fill and test package to one of the ends; using a submersible vehicle (SV) to operate at least one [subsea] high pressure pump on a fill and test package to raise the internal pressure of the pipeline sufficiently for a high-

Claim 7 (currently amended): A method for hydrostatic testing of a pipeline on the seafloor comprising:

pressure hydrostatic commissioning test.

using a submersible vehicle (SV) to operate one or more pumps <u>mounted</u> on a fill and test package, <u>including at least one high pressure pump dimensioned to provide a high-pressure hydrostatic test pressure</u>, to raise the internal pressure of the pipeline sufficiently for high-pressure hydrostatic testing.

Claim 8 (previously presented): A method for hydrostatic testing of a water filled pipeline on the seafloor comprising:

using a submersible vehicle (SV) to operate at least one high pressure pump on a fill and test package to pump water into said water filled pipeline to raise the internal pressure of the pipeline sufficiently for high-pressure hydrostatic testing.

Claim 9 (currently amended): A method for the hydrostatic testing of a pipeline between two subsea manifolds comprising:

using a submersible vehicle (SV) to <u>deploy and</u> operate one or more pumps on a fill and test package to pump seawater from near the seafloor into, and raise the internal pressure of, the pipeline sufficiently for high-pressure hydrostatic testing.